

## Addendum No. 2

## Project: Spindletop Silsbee Spindletop Center

Date: <u>3/9/2022</u>

All bidders are herewith notified of the following additions, deletions, changes or clarifications to the drawings dated 2/28/2022 and shall be acknowledged as received on the proposal.

1. Refer to Specification Section 015000

Due to limited parking on site, a Common-Use Field Office (job shack) will not be required. Contractor can utilize an area within the existing building for a field office.

2. Refer to attached A104 – Partition Plan

Contractor has the option of framing all <u>non-load bearing</u> typical interior partitions with 2x4 at 16 inches on center on treated plates, or 3 5/8" metal studs at 16 inches on center. Non-load bearing studs forming wet walls in Restroom 120, Restroom 138 and Shower 139 can be either 2x6's or 6" metal studs. All other load bearing partitions designated in red are to be 2x6's at 16" O.C., except studs at the two exterior corners are at 8" centers as noted on plan.

Studs shall extend from finish floor to underside of rafters in new addition, and from finish floor to underside of ceiling joists in the existing building. If used, 3 5/8" Metal stud Ga. shall be as follows:

- a. 3 5/8" studs up to 14 feet long 25 Ga
- b. 3 5/8" studs 14 feet to 18'-3" long -20 Ga

409.866.7196 www.architectall.com North, East and West walls of Lobby 100 shown in green are 2x8's at 16" O.C., except studs at the two exterior corners are at 8" centers as noted on plan.

3. Schluter Kerdi membrane shower system will we acceptable for tiled areas.

## End of Addendum # 2



Date: 3/9/2022

